

Notice to Contractors

The Town of Bradford will receive sealed bid notices until 5:00 p.m., Friday, May 3rd, 2019 at the office of the Town Clerk, Sandra Clarke, 11100 E. County Road MM, Avalon, WI 53505. On Monday May 6th, 2019 at the Town Board meeting commencing at 6:30 p.m. at the Bradford Town Hall, 3622 S. Carvers Rock Road, bids will be publicly opened and read aloud for labor, material, tools and equipment necessary for the following project:

Carvers Rock Road:

Culvert replacement:

At the junction of Carvers Rock Road and Town Hall Road remove the existing culvert on the south side of the intersection. Replace the culvert under Carvers Rock Road with three 24 foot long 18" aluminized steel, oval cross section culverts, banded together and ended with apron ends. Culvert, bands and apron ends will be purchased and provided by the Town of Bradford. Bring the area adjacent to the culvert up to grade using 3" breaker stone. Drape exposed culvert and area adjacent to apron with medium rip rap stone. Increase turn radius on east end of culvert, build up support for new radius and culvert with small rip rap and 3" stone as indicated. When paving over the culvert and roadway extend asphalt over the increased radius area.

Road reconditioning:

At the intersection of Carvers Rock Road and Bradford Town Hall Road saw cut termini as indicated on drawing. Full Depth pulverization of the indicated road surface 1,150 feet to south. Proof roll the area to determine if any underlying base is defective. State a square foot unit price for any base remediation. Increase inside radius of curve by 2 feet for a length of 130 feet as indicated. Upon completion of grading and compacting, tack coat area and place and compact 3" of HMA in two 1 ½" lifts. Using TB stone restore shoulder along entire surface to a width of 18"-24". Roadway dimensions and turn radius dimensions as per spec sheet.

Larsen Road:

At the intersection of Larsen Road and Carvers Rock Road to repair the west bound lane of Larsen Road, saw cut Larsen Road at Carvers Rock Road 63 feet wide, saw cut the radius with the eastbound lane and for the west boundary saw cut Larsen Road 143 feet from the intersection of Carvers Rock Road. Pulverize area full depth, grade and compact, proof roll and treat as per specs on Carvers Rock Road north of this site. Tack coat area, place and compact 3' of HMA placed in two 1 ½" lifts. Shoulder with TB stone 18" to 24" adjacent to all new asphalt. Reestablish ditch line on northwest corner of intersection with Carvers Rock Road. Re-contour and taper dirt build up away from road surface.

Contractor is to provide traffic control with appropriate signage.

REFER TO SPECIFICATION SHEET FOR ADDITIONAL INFORMATION. It is mandatory that contractors pick up specification sheet from the Town Clerk

Completion date to be determined by successful bidder and Town Board Chairperson

Address bids as follows:

Town of Bradford
Sandra Clarke, Clerk
11100 E. County Road MM
Avalon, WI 53505-9752

All bids are to be submitted in sealed envelopes, plainly marked for proper identification.

Bidding contractors MUST obtain drawing and specification documents from Sandra Clarke, Clerk at the above address.

The Town of Bradford reserves the right to reject any or all bids and to waive or not to waive any informalities in the bidding. The letting of the contract described herein is subject to provisions of Sections 66.0901 and 66.0903 of the Wisconsin Statutes.

After bids are opened, no bid can be withdrawn for a period of ninety (90) days thereafter.

Published by the authority of the Town Board of the Town of Bradford, this 18th day of April, 2019.

**Town of Bradford
Rock County, Wisconsin**

By: Sharon Douglas
Chairperson, Town of Bradford

Publish: 4/18 and 4/25/ 2019

In The Clinton Topper

